RealTest Construction

Project Proposal

SMA-QA-20261009T120012Z Crane Logistics West Jefferson (00420)

Reference: 260001

Prepared for: SMA-QA-20261009T120012Z Crane Logistics demo/pads (SYNTHETIC)
Prepared on: 10/9/2026
Prepared by: Cost Estimator

Proposal Summary

Base bid	$764,977.82
Selected alternates	$17,074.29
Allowances	$0.00
Contingencies	$0.00
TOTAL PROPOSAL	$782,052.11

BASE BID — SCOPE OF WORK

Description	Qty	Unit	Source	Total
[R11] General Conditions/Mobilization	1	EA	—	$58,463.00
[R13] Jeff Barker saw cut revised pricing	1	lump	—	$35,447.06
[R15] Cat 87-90 30,000lb w thumb x 2 for job per month	2	each	—	$33,000.00
[R16] fuel for machines	1	lump	—	$3,428.57
[R18] saw cut demo and haul off of 4 opeings per customer request	4	hours	—	$611.76
[R19] Jeff barker for 4 openings then cut into 3x3 piers 8" thk	1	lump	—	$33,588.24
[R20] haul and labor to load trucks	0.15	days	—	$642.86
[R23] haul spoils off site	294	hours	—	$3.00
[R24] rebar lbs 31752 lbs includes 2% fluff	31752	lbs	—	$38,102.40
[R25] 3" sbu chairs	2200	lf	—	$1,822.86
[R26] 25 each 3/4"x8" sds drill bits	25	each	—	$1,500.00
[R27] concrete yards for spreadasftgs 5.44 yds per pad x 162 each	1014	yards	—	$318,685.71
[R28] labor days demo $678.83 labor only	34	day	—	$145,714.29
[R29] labor days to pour spread ftgs $238.00 each labor only for pour back	9	days	—	$38,571.43
[R33] haul spoils off site	11	hours	—	$1,682.35
[R34] rebar 24#6 verts with #4 ties 10" oc	2275	lbs	—	$2,730.00
[R35] 50 lf 3" sbu chairs	50	lf	—	$41.43
[R36] concrete yards x 4 each 3'x3'x5' column ftgs at new openings	15	yards	—	$4,714.29
[R37] labor for demo anmd pour back	2.25	days	—	$9,642.86
[R38] mini ex day	1	days	—	$250.00
[R43] concrete yards 374 sf x 36" deep	48	yards	—	$15,085.71
[R44] rebar dowels into existing lump sum #5 24" oc x 16" long	1	lump	—	$928.57

[R45] skid steer days	1	days	—	$250.00
[R46] forming material	1	lump	—	$500.00
[R47] labor days $22.91 per sf labor only	2	days	—	$8,571.43
[R50] clean up days	2	days	—	$8,571.43
[R52] concrete washout containment rental	2	months	—	$2,428.57

Subtotal: $764,977.82

ALTERNATES

ALT-1 — Crackbond CSR self-leveling (src rows 55-57) [INCLUDED]

Description	Qty	Unit	Source	Total
[R56] 144 22 oz cartridges	144	each	—	$11,931.43
[R57] labor days	1.2	days	—	$5,142.86

Subtotal: $17,074.29